Kit Part Number: 700288

# **Breathe Safe**

Parts and Service Manual

LIEBHERR
R9600 EXCAVATOR

HEPA H14 Variable Speed Pressuriser | INPRESS TS Cabin Display with CO2 Sensor | HEPA Return Air Filter

+61 7 3276 7833

www.breathe-safe.com.au

≤ sales@breathe-safe.com

62 Mica Street, Carole Park, 4300, QLD

Controlled Document: M0223

Issue Date: 18/10/23

Revision: 3

R9600 Excavator



#### **INSTALLATION**

#### **CONTENTS**

Installation	1
Safety	2
Critical Parts & Maintenance Schedule	3
Operator Guide	4
Specifications - Pressuriser	5
Parts List	6-11
Technical Details1	<b>2-1</b> 3
Technical Details1	
	14
Leakage Test	14 15
Leakage Test  Cabin Sealing Test Pressure	14 15
Leakage Test  Cabin Sealing Test Pressure  Commissioning Procedures	14 15 16
Leakage Test  Cabin Sealing Test Pressure  Commissioning Procedures  Troubleshooting Guide	14 15 16 17

	INSTALLATION OVERVIEW						
Manufacturer	Liebherr						
Туре	Excavator						
Model	R9600						
Cabin Pressure Max							
Set Auto Cabin Pressure							





**HEPA H14 Variable Speed Pressuriser** 



**INPRESS TS Cabin Display with Data Recorder** 



**HEPA Return Air Filter** 

**R9600 Excavator** 



**SAFETY** 

#### **WARNING**

The pressurisation system described in this manual has the following areas which may be dangerous if not treated with great care.

Qualified staff must wear the correct personal protective equipment when cleaning and servicing this unit due to dust and fibres which may be caught by the stages of air filtration during normal unit operation.

The electrical power system is supplied by 12V DC or 24V DC, and no work should be carried out on the pressuriser system without the correct safe work procedures and electrical safety measures being taken, and all relevant circuit breakers opened to isolate the circuit.

The air filtration system may have several types of high-speed rotating equipment installed with very sharp edges. Ensure all safety guards are in place while the system is running.

Please be aware that HEPA filters cannot be cleaned and must be replaced at the end of their lifecycle or if the filter media has been damaged.
















#### **Particulate Behaviour**

This is the length of time it takes for a particle to drop from a height of 1.5m in **STILL** air.



Warehouses and workshops do not have still air, so hazardous airborne particulates may remain in air for longer, increasing chance for workers to breathe in dust. Ensure PPE is worn when installing this system.

This air quality system is designed to protect operators from harmful airborne contaminants. Keep the doors and windows closed at all times.

**R9600 Excavator** 



#### **CRITICAL PARTS & MAINTENANCE SCHEDULE**

#### **Maintenance Schedule**

The following tables show our suggested maintenance schedule for all units. Please note that site conditions may alter this. Excludes high corrosion environments.

Data download is required to claim the 3-year warranty on Brushless Blower Motor.

#### Inspect every 500 Hours and replace when filter is full\*

Component / System	Action Required
Turbo Pre-cleaner	Check operation of the Turbo Pre- Cleaner.
Pressuriser Blower	Ensure blower is operational.
HEPA Primary Filter p/n: <b>500000</b>	Inspect filter capacity indicator. Replace HEPA filter when 80% or greater. Vacuum out housing before replacing the filter elements.
HEPA Return Air Filter P/N: <b>500021 &amp; 500039</b>	Vacuum inside cabin floor before replacing filter.
Filter Frame Assembly, Mounts, Seals and Filter Housing	Check door seals, all bolts, screws, and all mounts are secure. Check the filter canister & ensure it is correctly fitted. Check latches are operational and in good order. Replace / Re-tension fixtures and fittings required.

#### 15,000 Hours / 36 months\*

Component / System	Action Required
500 Hour Inspection	All 500-hour inspection actions.
Pressuriser's Blower 200002	Replace BRUSHLESS Pressuriser blower.

	Critical Parts							
Item	Part Number	Qty.	Description	Service Interval				
1	500000	1	Fresh Air HEPA H14 Filter (Tested as per EN1822)	1000* Hours (>80% fan capacity)				
2	500021	4	HEPA Return Air Filter	500* Hours				
3	500039	2	HEPA Return Air Filter	500* Hours				
4	200002	1	Brushless Blower Motor – 24V	15,000 Hours				
5	200027	1	BreatheSafe Digital Display – Data Recorder (INPRESS TS)					

<sup>\*</sup>Filter service hours are subject to cab sealing efficiency, site conditions and correct system use.

#### **Suggested Schedule Servicing\***



#### **Fan Capacity Indicator**

The filter is serviceable if the motor capacity is between 10% & 80%. We recommend that the filter is changed if the capacity is over 80%.

\*Site dependent

**R9600 Excavator** 



#### **OPERATOR GUIDE**

	OPERATORS CHECKLIST						
	PRE-START PRE-START						
1.	Visually inspect the BreatheSafe system for any damage.						
2.	Visually inspect the cabin for any damage to doors, windows, seals.						
3.	Please remove dust & debris from shoes and clothes before entering the cabin.						
4.	Ensure door(s) and windows are closed correctly.						
5.	Start engine and turn HVAC on to speed 2 (medium speed).						
6.	After fixed speed delay, the BreatheSafe display will show 50 Pascals or pre-set value.						
	The system is working correctly when the pascal value is green.						
	>> There is no further action required <<						

#### NORMAL OPERATING CONDITION

#### **Cab Air Conditioning**

BreatheSafe recommends OEM air conditioning fan is set at mid speed or greater to circulate air around the breathing zone and minimise CO<sub>2</sub>.

Acceptable operating range for BreatheSafe fan 10-80%. >80% recommend maintenance.

# 8:30 22/04/2023 25% Cabin Pressure 50Pa CO2 Level 800 PPM

#### **ALERTS**

#### **Fixed Fan Start Delay**

• Allows the operator to carry out pre-start checks – limiting at 30% fan speed, press the red text to disable.

#### CO<sub>2</sub> Level Alert (if equipped)

• Ensure air conditioning fan is set at mid speed or greater to circulate air and minimise CO<sub>2</sub>.

#### **Low Pressure Alarm**

- Cabin is not maintaining positive pressure check doors and windows are closed correctly.
- Refer to maintenance department to check filters and cabin sealing. Ensure filters are serviceable.

#### **Check Filter**

- Reminder to inspect or replace filter. Service hour meter requires re-set.
- Refer to maintenance department.



R9600 Excavator

### **Breathe Safe**

Item No.	Qty.	Description	Part No.
1	1	Pre-cleaner Hood & Rotor Assy	200004
2	4	Pre-cleaner Injector Ring	200005
3	1	TL Fan Blade (inc. in #7)	200006
4	1	TL Nose Cone / Pre-cleaner	200007
5	1	TL Motor Housing	200008
6	1	TL Filter Housing	200009
7	1	24v DC Brushless VSD Motor & TL Fan Blade	200002
8	1	O Ring Seal Kit 2 Parts	200010
9	1	Included in 8	200011
10	1	Wiring Sleeve	200012
11	1	HEPA H14 Filter	500000
12	3	M6 Nyloc Nut	300218
13	3	M6 x 55mm Hex Bolt	300982
14	4	M8 x 190 Hex Bolt	301136
15	8	M8 x 22mm O/D HD Washer	300230
16	4	M8 Nyloc Nut	300249
17	5	M4 x 75mm Pan Head Phillips Screw	300162

Specifications –	High-Capacity HEPA Pressuriser
Blower	High RPM Brushless VSD
Protection	Locked rotor, under/over voltage, under/over current & over
	temperature
Voltage	24VDC
<b>Current Draw</b>	11 A maximum. Blower programmed with slow start to stop
	excessive in-rush current
Air Flow	30-300 m3 /hr (50-215 CFM)
Pre-Cleaner	Integrated VLR (Very Low Restriction) mechanical pre-cleaner
Filter Element	BreatheSafe HEPA H14 Primary Filter (99.995% @ MPPS)
Connector	Mining Spec. Deutsch electrical connectors as standard
Materials	High strength composite
Serviceability	Single part filter assembly with twist-lock (TL) cap
Mounting	Heavy duty adjustable mounting brackets
Design	100% designed by BreatheSafe engineering




R9600 Excavator



Item No.	Part No.	Rev	Description	Qty	Colour	Category
1	100298A01	3	High Pressure Unit Module	1	Black Satin 27219268	Weld Assy
2	100298P01	2	Pipework Module	1	Black Satin 27219268	Pipework
3	100298M01	2	Monitor Module	1	Charcoal Satin 27288351	Module
4	100298R01	2	Return Air Module	1	Charcoal Satin 27288351	Module

PARTS LIST GA

**COMPLETE ASSEMBLY No: 700288** 





R9600 Excavator

### **Breathe Safe**

Item No.	Part No.	Rev	Description	Qty	Material	Thickness	Colour	Category
1	100298A02	1	TL Mount Assy	1	-	-	Black Satin 27219268	Weld Assy
2	100298A03	2	TL Cover Assy	1	-	-	Black Satin 27219268	Weld Assy
3	100298A04	1	Channel Mount	1	-	-	Black Satin 27219268	Weld Assy
4	100298A05	0	Channel Mount with Bracket	1	-	-	Black Satin 27219268	Weld Assy
5	300483	-	Stauff GR7 Weld Plate	1	Zinc Plated	5	(As Req'd)	Pipework
6	200000	[*]	TL4 24V DC Unit	1	-	-	-	Stock Item
7	250007	0	TL Mount Bracket 56.5mm	1	Mild Steel	3	(As Req'd)	Stock Item
8	301016	-	Bolt PHCSK M8x20L 12.9	4	Zinc Plated	-	-	Fasteners

#### PARTS LIST – PRESSURISER MODULE






R9600 Excavator

**Breathe Safe** 

Item No.	Part No.	Rev	Description	Qty	Material	Thickness	Colour	Category
1	300388-0070	-	76.3 x 1.6 @70mm	1	Stainless Steel	1.6	(As Req'd)	Pipework
2	300388-0200	-	76.3 x 1.6 @200mm	1	Stainless Steel	1.6	(As Req'd)	Pipework
3	300001	-	65-89mm Hose Clamp	6	-	-	-	Pipework
4	776.1-PA-DP	-	Stauff – 3" Clamp Assy	1	PA Type 6	1.6	-	Pipework
5	3"-90Deg	-	3"x90* Elbow Long Drop Sil	2	Silicone	-	-	Pipework
6	200308	0	3"-90Deg Short Elbow	1	Silicone	-	-	-

#### PARTS LIST – PIPEWORK MODULE




R9600 Excavator

**Breathe Safe** 

Item No.	Part No.	Rev	Description	Qty	Material	Thickness	Colour	Category
1	100298-M277	1	Monitor Bracket	1	Mild Steel	3	Charcoal Grey MX83-682	Part
2	250100	0	Monitor Box, Small	1	-	-	(Per Assy Colour)	Stock Item
3	250106	0	CO2 Bracket Universal	1	-	-	-	Stock Item

#### PARTS LIST – MONITOR MODULE




R9600 Excavator

**Breathe Safe** 

Item No.	Part No.	Rev	Description	Qty	Material	Thickness	Colour	Category
1	100298R03	0	Filter Frame Weldment	1	-	-	Charcoal Satin 27288351	Weld Assy
2	100298R04	1	Filter Cover Weldment	4	-	-	Charcoal Satin 27288351	Weld Assy
3	300814	-	M6x20 Scallop Knob Male	8	-	-	-	Hardware
4	500021	[*]	HEPA Filter 375 x 140 x 40	4	N/A	-	-	HEPA Filter

PARTS LIST – RETURN AIR MODULE




R9600 Excavator

**Breathe Safe** 

Item No.	Part No.	Rev	Description	Qty	Material	Thickness	Colour	Category
1	100298R06	1	Filter Frame Weldment	1	-	-	Charcoal Satin 27288351	Weld Assy
2	100298R07	1	Filter Cover Weldment	2	-	-	Charcoal Satin 27288351	Weld Assy
3	300814	-	M6x20 Scallop Knob Male	4	-	-	-	Hardware
4	500039	[*]	HEPA Filter 320 x 150 x 31	2	-	-	-	HEPA Filter

PARTS LIST – RETURN AIR MODULE



**R9600 Excavator** 




#### **TECHNICAL DETAILS**

#### **Display Key Features**

- Digital cabin pressure monitoring system
- Automatic cabin pressure control
- Intelligent fan speed output
- Data logger
- Alarm for low-pressure (RS20)
- Light sensor for automatic dimming of the screen








MAIN SCREEN
Options\* when fitted

#### **CO2 Sensor**

- CO2 Sensor Type is NDIR (Non-Dispersive Infrared)
- Sample Rate is every 2 seconds
- 12-30V DC Operating Voltage
- Automatic Altitude Compensation
- Alarm Set points are adjustable
- No setup required



#### Wiring Diagram - InPress Controller

#### **WIRING DIAGRAM**


Qty

1

1

1

1





**R9600 Excavator** 

### **Breathe Safe**

#### Hand-Held Differential Pressure Monitor (HHDPM) Leakage Test

Test enclosure for air leakage using the HHDPM.

#### Cabin Pressure: Sensor outside the cabin

The cabin pressure test can also be carried out with the service technician outside the cabin.

- 1. With the door open, turn on the HHDPM and observe the pressure reading. Confirm it is reading zero.
- 2. Connect the pressure reference tube to 'Positive' (top port) place the other end of the tube on the operator seat, away from HVAC vents and any other direct airflow.
- 3. Turn on the machine's HVAC and pressurisation system (if present). Ensure HVAC is set to fresh air and not recirculation.
- 4. Close the door, make sure the tube isn't kinked.
- 5. Observe the pressure reading and allow it to stabilise. The handheld differential pressure monitor & cabin pressure monitor should read within 5 Pa of each other.
- 6. Feel around the enclosure for any pressure leaks. Seal enclosure where leaks are present and monitor pressure changes.

#### Part Number: 200142

1. Positive Pressure Port

2. Ambient Pressure Port

- 3. Charging LED
- 4. Charging Port
- 5. Re-Zero Button
- 6. Power Button
- 7. Display



#### **Typical Seal Locations:**


- Lower pillar openings
- Upper pillar openings where necessary
- Cabin frame
- Floor plates either internal or external foam tape etc.
- Door seals
- Window seals
- Exterior access panels
- Hydraulic hose entrance points




#### **CABIN SEALING TEST PROCEDURE**

	Cabin Sealing Efficiency Test Procedure				
1	New replacement filter is required to perform this check. Start engine (pressuriser ON) and ensure all windows & door(s) are CLOSED correctly (no cabin pressure leaks).				
5	Pressure target is 250 Pa or greater with a new filter. Less than 250 Pa requires cabin sealing improvements.				


#### InPress (Touch Screen)



2. Press the settings cog.



3. Press 'SYSTEM CHECK SET MAX' button.



4. Record results. Repeat steps 1 & 2 to finish test.

**R9600 Excavator** 



#### **Commissioning Procedures**

#### **COMMISSIONING PROCEDURES – CABIN PRESSURISER**


#### Follow each step of the installation guide that was supplied with the BreatheSafe kit.

Cabin sealing is an integral part of RS20 & ISO 23875; you must ensure that cabin seals are adequate for maintaining positive pressure. In addition, the site (end- user) must have the correct procedure(s) for servicing OPERATOR enclosure seals in a proactive manner rather than reactive. Items such as door and window seals must be in good working order or new seals FITTED before the BreatheSafe system installation.

Touch-screen cabin pressure display/controller Part# 200027:

\*System Check Function: enter the Settings menu option and select "System Check – Set Max." The minimum BreatheSafe requirement for cabin sealing efficiency is 250 pascals; if this result is not met, it is essential to re-examine and find pressure leaks of the enclosure and apply new sealing measures.

Submission for commissioning procedure as per the diagram below:





#### The commissioning images required are:

- ID plate / Machine Serial Number / Asset Number or Call Sign
- INPRESS TL Pressuriser location
- HEPA Return Air Filter Location Option: Powered Return Air Filter
- Cabin Pressure Display Location Including the "System Check" maximum cabin pressure result with motor output capacity %

Fill in the BreatheSafe Service Tag with the following details:

- Machine Serial Number and Installers details
- Date installed and System Check result (max cabin pressure)
- The set cabin pressure with actual pressure and motor percentage output
- Verify the 250-pascal threshold was achieved = pass OR not achieved = fail\*\*

Please upload machine and installation details in conjunction with the required images. A Commissioning Certificate will be sent to the email address you nominate. \*\*Extended warranty for (RS20 & ISO 23875) BreatheSafe Systems is only applicable to operator enclosures meeting this requirement.

<b>Breathe</b> Sa	5 (40 (63.63))				
AIR CONDITIONING FAN MUST BE TURNED	Part of Aire Safe  AIR CONDITIONING FAN MUST BE TURNED TO MEDIUM SPEED TO CIRCULATE AIR & MINIMISE CO, LEVELS.				
MACHINE SN:	BREATHESAFE CONTROLLER SN:				
DATE INSTALLED:	MACHINE HOURS:				
AUTO PRE-SET PRESSURE (Pa): MAX CABIN PRESSURE (Pa):					
NOTES (FILTER PART NUMBERS):					
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16	17 18 19 20 21 22 23 24 25 26 27 28 29 30 31				
JAN FEB MAR APR MAY JUN	JUL AUG SEP OCT NOV DEC				
2023 2024 2025	2026 2027 2028				
Technical Support Phone: 1300 66	57 597   www.breathe-safe.com				



R9600 Excavator



FAULT	POSSIBLE CAUSE	SOLUTION	
ERR error code	Poor sensor connection	Remove & refit pod connection cable	
	Corrupted coding	Contact support for default reset pin	
Check filter alarm	Service hour timeout	Access <i>Check Runtime</i> menu - reset hours via 7597 code	
emperature / CO2 error	Sensor not connected	Fit sensor or disable via site access CO2 & or temperature menu	
ressuriser running at full speed/noisy	Filter blocked	Service filter	
. , ,	Door or window open	Ensure doors & windows securely shut	
	Cabin sealing capacity not adequate	Perform pressure test procedure & seal leak points as required	
	Sense pipe blocked	Ensure clear & not bent	
	Internal sensor damaged	Replace controller	
		**No need to change setpoint	
ilter blocking quickly	Defective cabin sealing	Perform pressure test procedure & seal leak points as required	
	Pre-cleaner failed	Check operation & replace if necessary	
isplay blank	Poor power supply	Check mains supply fuse & correct voltage	
		Check voltage & 20AMP supply/connections at pin 1 @ monitor	
		Check earth continuity at controller pin 12	
	Failed controller	Replace monitor	
ontroller showing 0.0 pressure	Fresh air filter blocked	Check filter condition & replace if required.	
ow pressure alarm	Door or window open	Ensure doors & windows securely shut	
	Cabin sealing capacity not adequate	Perform pressure test procedure & rectify cab sealing	
	Pressuriser not operating	Ensure correct voltage 12v or 24v to pressuriser motor pin A	
		Check 1.6V - 10V present at motor Pin C	
		Check 20A Supply fuse	
		Check earth continuity Pin <b>B</b>	
	Pressure sense tube blocked	Unplug at monitor & ensure clear flow to external of cabin	
		Ensure pressure tube fitted correct port A	
		**No need to change setpoint	
ressuriser not working	Poor power supply	Check 20A mains fuse & correct voltage	
		Ensure adequate wire size & no voltage drop	
		Ensure correct voltage 12v or 24v to pressuriser motor pin A	
		Check 1.6V - 10V present at motor Pin C	
	Poor earth	Check earth continuity @ motor pin B	
	Motor faulty	Replace TL4M	
Access Codes:	Site Access: 7597	Contact Support for Factory Setup Pin	

**R9600 Excavator** 

### **Breathe Safe**

#### **User Settings Instructions**


#### **ENTER SET UP MODE**

Start-Up Screen > Main Screen > Settings Button > Settings Screen > Site Access Button > Insert Pin > Site Menu

To enter the Setup mode, press the SETTING button.

Then enter SITE ACCESS MENU. Type in 4-number pin and press ENTER.

Insert Pin = 7597




#### **SET UP PARAMETERS**


Placing the BreatheSafe 200027 unit into Setup mode allows the adjustment of the following parameters:

- Time (hours/minutes/seconds)
- Date (day/month/year)
- Pressure alarm setpoint
- Preferred cabin pressure
- Alarm delay/ intervals of alarm
- Calibration and system settings
- Resetting of the data logging
- Service reminders interval gap
- Reset current runtime between services
- CO2 settings and alarms

#### **USER SETTINGS INSTRUCTIONS**







**R9600 Excavator** 

### **Breathe Safe**


#### PRESSURE SETPOINT


The pressure setpoint changes the pressure that the cabin will be maintained. INPRESS TS maintains the pre-set pressure within the cabin compared to outside.

Enter Setup mode and select ADJUST SETPOINT button. Then, use the onscreen UP and DOWN buttons to change the corresponding fields.


4













#### PRESSURE ALARM SETTING


**USER SETTINGS INSTRUCTIONS** 

The mining industry benchmark for cabin pressure is 50 pascals and low-pressure is set at 20 pascals.


After a delay the alarm will activate if cabin pressure remains below the pre-set value. Enter Setup mode and select ADJUST SETPOINT button. Then, use the onscreen UP and DOWN buttons to change the corresponding fields.












**R9600 Excavator** 

### **Breathe Safe**


#### SERVICE INTERVAL

Use the onscreen UP and DOWN buttons to change the service interval setpoint.


To reset the current runtime to zero, press the RESET CURRENT RUNTIME button and enter the site access pin.














#### **DATE & TIME SETTINGS**


**USER SETTINGS INSTRUCTIONS** 


Change the recorded date displayed and measured by the INPRESS TS.













R9600 Excavator


### **Breathe Safe**

#### PRESSURE ALARM BUZZER SETTING


To disable the buzzer, toggle through to the ENABLED and DISABLED buttons.
















#### **CALIBRATE ZERO SENSOR**

**ALARM BUZZER SETTINGS** 


Over long runtime, the 200027 may need recalibration. This screen allows the sensor to be recalibrated if more than 5 Pascals are out. To recalibrate, open windows and doors, turn off air conditioning, and any other device that may alter cabin pressure. Then, press the AUTO ZERO SENSOR button and leave the cabin while measuring. This process will reset the Zero Pressure.














**R9600 Excavator** 

### **Breathe Safe**


#### CO2 MODULE ENABLE/DISABLE


Enable or disable to CO2 module used for measuring CO2 levels within the cabin.


#### **CO2 PRIMARY ALARM POINT**

**CO2 SETTINGS** 

The first alarm will sound when CO2 levels inside the enclosure reach this point.








BACK

CO2 ALARM

DELAY


2 Min








ALARM

MUTE DELAY












**R9600 Excavator** 


### **Breathe Safe**

#### **CO2 ALARM DELAY**


After CO2 (concentration in ppm) within the cabin reaches the 1000 ppm setpoint, the alarm will sound after this designated amount of time. The Alarm Delay adjusts the time between the INPRESS TS measuring CO2 concentration and sounding the alarm. Use the onscreen ADJUST buttons to change the corresponding fields. For example, press to toggle through Disabled / 1 - 10 minutes.














#### **CO2 CRITICAL ALARM MUTE RESET**

**CO2 SETTINGS** 


The critical alarm is set at 2500 PPM and cannot be changed. The mute delay, however, can be configured.













**R9600 Excavator** 


### **Breathe Safe**

#### Data Download - Setting up RS232 Connection




- Plug the RS232/USB adaptor into a free USB port on your computer.
- 2 Open up TeraTerm software.


(*TeraTerm* is an open-source software tool and easily accessible via online search)




Click on the COMxx Port with the "USB serial Port" connection from the dropdown menu.

Example: COM 4 This connection may be different on your computer.







#### **DATA DOWNLOAD**

Click OK once the correct communication port has been identified.

Go to SETUP and click on Serial Port.

6 Change the COM ports to the following configuration:


Baud

Rate: 57600 Data: 8 bit

Parity: EVEN

Stop: 2 bit


Flow Control: NONE



**R9600 Excavator** 

### **Breathe Safe**


#### Data Download - Setting up RS232 Connection




7 If required, you may choose to save the COM port settings. Go to Settings and click save the setup.


Hint: From the drop-down menu, click on the Save Setup.

Name the file and save it.



The next time a download is required, you may restore the setup, and the required COM PORT settings will be loaded, ready to download the data file from the 200027 unit.





#### **DATA DOWNLOAD**


From the drop-down menu, click on Restore setup.

10 Choose the file name you have already saved.


**R9600 Excavator** 

### **Breathe Safe**


#### **INPRESS Controller Set Up**




1. Press 'SITE ACCESS MENU'.



2. Enter the access pin '7597'.



3. Press 'NEXT'.



4. Press 'LOG SETTINGS'.

**CONTROLLER SET UP** 



5. Press 'DOWNLOAD LOG FILE'.





 Data is now downloading from controller to terminal open on the computer (TeraTerm in this example).

**R9600 Excavator** 



#### Data Download - Copying Contents from Terminal to Spreadsheet





4	Α	В	С	D	E	F
1	DATE	TIME	MOTOR (VOLT) OUTPUT	CABIN PRESSURE PA	CABIN PRESET PA	CO2 Sensor
2	12/11/2023	16:43	2.1	50	50	600
3	12/11/2023	17:44	2.1	50	50	596
4	12/11/2023	18:46	2.1	51	50	601
5	12/11/2023	19:47	2.1	50	50	603
6	12/11/2023	20:48	2.1	50	50	595
7	12/11/2023	21:50	2.1	50	50	593
8	12/11/2023	22:51	2.1	50	50	591
9	12/11/2023	23:52	2.1	50	50	588
10	13/11/2023	0:54	2.1	51	50	595
11	13/11/2023	1:55	2.1	50	50	582
12	13/11/2023	2:56	2.1	50	50	587
13	13/11/2023	3:58	2.1	51	50	593
14	13/11/2023	4:59	2.1	50	50	598
15	13/11/2023	6:00	2.1	51	50	742
16	13/11/2023	7:02	2.1	51	50	767

12 From the drop-down menu, click on the Edit menu function.

13 Press "Select All".

14 Select "Copy table".

Open a blank excel document and click on the page. Then, right-click to paste the copied table.

16 Fields are:

Date, time, motor (volts) output (e.g. 5.5 = 55%), cabin pressure (Pa), cabin pressure pre-set (Pa), CO2 sensor.

#### **DATA DOWNLOAD**

#### Excel Data Instructions – Unformatted

Open an Excel sheet and select the first cell A-1. Next, press and hold down the CTRL button on your keyboard and then press the letter V on the keyboard.

This procedure will paste the copied data onto that Excel sheet. Once that data has been pasted onto the Excel sheet, click on 'DATA' on the pull-down menu, followed by 'Text to Columns'. Next, select 'Delimited' on the newly opened window and click on Next.

Only select the 'Comma' button in the next window and then click 'Finish'. Then, the Excel fields will update such that each piece of data is placed in the correct columns.

The data is now ready for archiving.

#### **Data Logging Formats**

BU No: xxxxxx (the device number unique to each unit and used for identification – format = 000000)

Time: [09:25]

Date: [25/07/12]

Pressure: 32 (Pascals) as an example.

Alarm Type				
0	= No alarm			
1	= Low-pressure alarm			
2	= Window open			
3	= Door open			





**AUDIT & WARRANTY** 

**Audit Your System Here:** <u>Audit Registry</u> (https://atreg.breathe-safe.com.au/audits)

**BreatheSafe Warranty:** <u>Warranty - BreatheSafe</u> (www.breathesafe.com.au/warranty/)